

## Subdivisional Lines, T 5 N R 34 E W M.

Chains	N. bet. Secs. 8 & 9.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post, in ravine. Drove charred stake; dug pits and raised mound, as per instructions.
80.00	Set post Cor. for Secs. 4, 5, 8 & 9. Drove charred stake; dug pits and raised mound, as per instructions. Land; broken. Grass good. Soil; 2nd rate.
	April 15th.
	E. on random bet. Secs. 4 & 9.
40.00	Set temp. $\frac{1}{4}$ Sec. post Cor.
80.06	Intersect N. & S. line, 42 lks. S. of post, from which, I run S. 89° 42' W. on true line.
40.03	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.
80.06	To post Cor. Land; quite broken. Soil; good 2nd rate.
	N. on random bet. Secs. 4 & 5.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.46	Intersect N. Tp. line, 52 lks. E. of post, from which, I run S. 22' E. on true line.
40.46	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions. Land; very broken. Grass good. Soil; 2nd rate.