

1.

Exterior Lines,  
 N. Bdy., T 5 N R 35 E W M.,  
 As surveyed by Odell and Lewis, U.S. Deputy Surveyors,  
 Under Contract No. 110,  
 Dated Feby. 7th, 1865.

Chains

W. on N. Bdy. of Sec. 1, on random

Var. 21° E.

Mar. 25, 1865.

35.50 Wagon road, course N.E.

37.50 Enter creek bottom.

40.00 Set post Cor. for  $\frac{1}{4}$  Sec.

Drove charred stake & raised stone mound, as per instructions.

43.25 Creek, 75 lks. wide, course N.

51.60 " 50 " " " "

65.50 Road, course N.

80.00 Set temp. post Cor. for Secs. 1, 2, 35 & 36.

Land; level.

Soil; 2nd rate, on E. half; on W., rocky.

Mar. 27, 1865.

W. on N. Bdy. of Secs. 2 on random

Var. 21° E.

4.40 Creek, 25 lks. wide, course N.

9.00 " 20 " " " "

17.25 " " " " " "

40.00 Set temp.  $\frac{1}{4}$  Sec. post on level.

80.00 Set temp. post Cor. for Secs. 2, 3, 34 & 35.

Land; level.

Soil; 1st rate between the creeks, W. gravelly.

Good grass.

Mar. 28, 1865.

W. on random on N. Bdy. of Secs. 3.

Var. 21° E.

7.60 Road, course N\*W.

40.00 Set temp.  $\frac{1}{4}$  Sec. Post.

80.00 Set temp. Sec. Cor. post.

Land, level.

Soil; 2nd rate.

Good grass.