

Exterior Lines, T 5 N R 35 E W M.

E. Bdy..

Chains

80.00 Set post Cor. for Secs. 13 & 24, 18 & 19, on steep hillside facing E.
Drove charred stake; dug pits & raised mound, as per instructions.
This line passes along hillside, facing E., bordering on small creek.
Good grass.
Soil; good 2nd rate.

N. on E. Bdy. of Secs. 13. H

Var. 21°E.

40.00 Set post Cor. for $\frac{1}{4}$ Sec.
Land gently descending to N.E.

49.75 Bank of Walla Walla River, 150 lks. wide, course N.W.

52.25 Enter timber.

80.00 Set post Cor. for Secs. 12, 13, 7 & 18; from which
A balm, 10 ins. diam., brs. N.34°E., 81 lks. dist.
A " 6 " " " N.62°W., 97 " "
A " 6 " " " S.36°15'W., 124 lks. "
A " 7 " " " S.45°30'E., 117 " "
This line, for the first half, passes down E. slope of hill.
Good grass.
Soil; 2nd rate.
From the river the line passes over low bottom land, stony.
Timber; balm.

N. on E. Bdy. of Sec. 12. H

Var. 21°E.

23.00 Leave timber and commence to ascend hill.

40.00 Set post Cor. for $\frac{1}{4}$ Sec. on ridge. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 1, 12, 6 & 7.
Land gently slopes to N.E. Drove charred stake; dug pits