

Subdivisional Lines, T 5 N R 35 E W M.

Chains	N. bet. Secs. 23 & 24.	
		Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post Cor.	
	Drove charred stake; dug pits; raised mound, as per instructions.	
80.00	Set post Cor. for Secs. 13, 14, 23 & 24. Drove charred stake;	
	dug pits; raised mound, as per instructions.	
	Land gently rolling.	
	Good grass.	
	Soil; good 2nd rate.	
		A
	E. on random bet. Secs. 13 & 24.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
80.05	Intersect N. & S. line, 15 S. of post, to correct run	
	S. 89°54'W. on true line.	
32.75	Road, course W. of N.	
40.02 $\frac{1}{2}$	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits; raised	
	mound, as per instructions.	
80.05	To post Cor.	
	Land; rolling. Good grass.	
	Soil; 2nd rate.	
		A
	N. bet. Secs. 13 & 14.	
		Var. 21°E.
31.50	Road, course N.W.	
40.00	Set post Cor. for $\frac{1}{4}$ Sec. Drove charred stake, etc.	
80.00	Set post Cor. for Secs. 11, 12, 13 & 14. Drove charred	
	stake; dug pits; raised mound, as per instructions.	
	The land on this line is gently rolling, with good grass.	
	Soil; good 2nd rate.	
		A
	E. on random bet. Secs. 12 & 13.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	Var
79.89	Intersect N. & S. line, 20 lks. S. of post. Hence the cor-	