

Subdivisional Lines, T 5 N R 35 E W M.

Chains	E. on random bet. Secs. 11 & 14.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
56.00	Road, course N.
79.90	Intersect N. & S. line, 40 lks. N. of post; from which I run
	W. on true line, course N.89°43'W.
39.95	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.90	To post Cor. for Secs. 10, 11, 14 & 15. Land; broken. Grass good. Soil; 2nd rate.
N. bet. Secs. 10 & 11.	
	Var.21°E.
40.00	Set $\frac{1}{4}$ Sec. post; dug pits; raised mound, as per instructions.
80.00	Set post Cor. for Secs. 2, 3, 10 & 11; drove charred stake; dug pits & raised mound, as per instructions.
	Land; rolling. Grass good. Soil; 2nd rate.
E. on random bet. Secs. 2 & 11.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
65.00	Summit of hill.
65.50	Foot of hill.
79.94	Intersect N. & S. line, 16 lks. N. of post; from which, I run
	W. on true line, course N. 89°53'W.
39.97	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.94	To post Cor. for Secs. 2, 3, 10 & 11. Land; broken. Grass good. Soil; 2nd rate.