

Subdivisional Lines, T 5 N R 35

Chains	
	N. bet. Secs. 32 & 33.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 28, 29, 32 & 33; drove charred; dug pits & raised mound, as per instructions.
	Land; gently rolling.
	Grass good.
	Soil; 2nd rate.
	E. on random bet. Secs. 28 & 33.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.10	Intersect N. & S. line at post; from which, I run W. on true line.
40.05	Set post Cor. for $\frac{1}{4}$ Sec.; drove charred stake; dug pits; raised mound, as per instructions.
80.10	To post Cor. for Secs. 28, 29, 32 & 33.
	Land; rolling.
	Grass good.
	Soil; 2nd rate.
	N. bet. Secs. 28 & 29.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 20, 21, 28 & 29. Drove charred stake; dug pits and raised mound, as per instructions.
	Land; broken.
	Grass good.
	Soil; 2nd rate.
	E. on random bet. Secs. 21 & 28.
40.00	Set temp. post for $\frac{1}{4}$ Sec. Cor.
80.44	Intersect N. & S. line, 30 lks. N. of post; from which, I run