

Subdivisional Lines, T 5 N R 35 E W M.

Chains	<p>80.00 Set post Cor. for Secs. 8, 9, 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions.</p> <p>Land; rolling.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
<p>April 12, 1865.</p>	
E. on random bet. Secs. 9 & 16.	<p>40.00 Set temp. $\frac{1}{4}$ Sec. post.</p> <p>80.30 Intersect N. & S. line, 20 lks. S. of post Cor. for Secs. 9, 10, 15 & 16; from which, I run S.89°49' W. on true line.</p>
40.15 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	<p>80.30 To post Cor. for Secs. 8, 9, 16 & 17.</p> <p>Land; rolling.</p> <p>Good grass.</p> <p>Soil; 2nd rate.</p>
N. bet. Secs. 8 & 9.	<p>Var.21°E.</p>
40.00 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	<p>80.00 Set post Cor. for Secs. 4, 5, 8 & 9.</p> <p>Drove charred stake; dug pits & raised mound, as per instructions.</p> <p>Land; rolling.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
E. on random bet. Secs. 4 & 9.	<p>26.00 Cross ditch, fence & enter field, course N. & S.</p> <p>30.50 Dry Creek, 25 lks. wide, course N.W.</p> <p>39.75 Leave field.</p>