

## Subdivisional Lines, T 5 N R 35 E W M.

Chains	E. on random bet. Secs. 29 & 32.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.70	Intersect N. & S. line, 20 lks. S. of post Cor. for Secs. 28, 29, 32 & 33; from which, I run S.89°51' W. on true line.
39.85	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.70	To post Cor. for Secs. 28, 29, 32 & 33. Land; rolling. Grass good. Soil; 2nd rate.
	W. on random bet. Secs. 30 & 31.
1.00	Pine Creek, 30 lks. wide, course N.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.80	Intersect N. & S. line at post Cor. for Secs. 30, 31, 36 & 25; from which, I run E. on true line
39.80	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.80	To post Cor. for Secs. 29, 30, 31 & 32. Land; rolling. Grass good. Soil; 2nd rate.
	N. bet. Secs. 29 & 30. Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
42.00	To bend in Pine Creek, course N.
80.00	Set post Cor. for Secs. 19, 20, 29 & 30, on steep hillside, facing W.; drove charred stake; dug pits & made mound, as per instructions. Land; broken.