

Subdivisional Lines, T 5 N R 35 E W M.

Chains	<p>mound, as per instructions.</p> <p>80.00 Set post Cor. for Secs. 7, 8, 17 & 18; drove charred stake; dug pits & raised mound, as per instructions.</p> <p>Land; broken.</p> <p>Grass good.</p> <p>Soil; 2nd rate.</p>
	<p>April 15, 1865.</p>
	<p>E. on random bet. Secs. 8 & 17.</p> <p>40.00 Set temp. $\frac{1}{4}$ Sec. post.</p> <p>80.25 Intersect N. & S. line, 45 lks. S. of post Cor. for Secs. 8, 9, 16 & 17; from which, I run</p> <p>S.89°43' W. on true line.</p> <p>40.12 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.</p> <p>80.25 To post Cor. for Secs. 7, 8, 17 & 18.</p> <p>Land; broken.</p> <p>Good grass.</p> <p>Soil; 2nd rate.</p>
	<p>W. on random bet. Secs. 7 & 18.</p> <p>36.00 Pine Creek, 25 lks. wide.</p> <p>40.00 Set temp. $\frac{1}{4}$ Sec. post.</p> <p>79.50 Intersect N. & S. line, 28 lks. S. of post Cor. for Secs. 7, 12, 13 & 18; from which, I run</p> <p>S.89°48' E. on true line.</p> <p>39.50 Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.</p> <p>79.50 To post Cor. for Secs. 7, 8, 17 & 18.</p> <p>Land; broken.</p> <p>Grass poor.</p> <p>Soil; 3rd rate.</p>
	<p>N. bet. Secs. 7 & 8.</p> <p style="text-align: right;">Var. 21° E.</p>