

Subdivisional Lines, T 5 N R 35 E W M.

Chains	
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 5, 6, 7 & 8; drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; 2nd rate. Soil; poor 2nd rate.
	E. on random bet. Secs. 5 & 8.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.85	Intersect N. & S. line, 60 lks. S. of post; Cor. for Secs. 4, 5, 8 & 9; from which, I run S. $89^{\circ}34'$ W. on true line.
39.92	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.85	To post Cor. for Secs. 6, 7, 5 & 8. Land; broken. Grass good. Soil; 2nd rate.
	W. on random bet. Secs. 6 & 7.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.17	Intersect N. & S. line, 52 lks. N. of post; from which, I run N. $89^{\circ}39'$ E. on true line.
40.17	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits and raised mound, as per instructions.
80.17	To post Cor. for Secs. 5, 6, 7 & 8. Land; broken. Grass poor. Soil; gravel.
	April 16th, 1865.
	N. on random bet. Secs. 5 & 6. Var. 21° E.