

Exterior Lines, T 5 N R 36 E W M.
 East Bdy.
 As surveyed by Odell & Lewis, U.S. Deputy Surveyors,
 Under Contract No. 110,
 Dated Feby. 7th, 1865.

Chains

N. on E. Bdy. of Sec. 36.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post on side hill, sloping to E. Drove charred stake; dug pits & raised mound, as per instructions.

66.00 Walla Walla River, (S. Fork), course W.

80.00 Set post Cor. for Secs. 25, 36, 31 & 30. Drove charred stake; dug pits & raised mound, as per instructions.

Land; very broken.

Grass; poor

Soil; 2nd rate.

N. on E. Bdy. of Secs. 25.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. Post. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 24, 25, 19 & 30, on steep hillside facing N. Drove charred stake; dug pits & raised mound as per instructions.

This line passes over high ridge, divide bet. N. & S. Forks of the Walla Walla River.

Grass; good.

Soil; 2nd rate.

N. on E. Bdy. of Secs. 24..

Var. 21° E.

23.70 Walla Walla River, course W.

29.00 Road, course W.

40.00 Set $\frac{1}{4}$ Sec. post on ridge, facing S. W. Drove charred stake; dug pits & raised mound, as per instructions.

54.00 Spring branch, course S.W.

80.00 Set post Cor. for Secs. 13, 24, 18 & 19. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Grass; good.

Soil; 2nd rate.