

Subdivisional Lines, T 5 N R 36 E W M.

Chains

40.00 Set $\frac{1}{4}$ Sec. post on steep hillside, facing deep canyon to the W. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 25, 26, 35 & 36, on high hill, sloping to N. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Grass; 2nd rate.

Soil; poor 2nd rate.

E. on random bet. Secs. 25 & 36.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

79.70 Intersect N. & S. T₂ line, 30 lks. N. of post; from which I run

N.89°47'W. on a true line.

39.75 Set $\frac{1}{4}$ Sec. post, on E. side of steep hill, one chain from summit. Drove charred stake; dug pits and raised mound, as per instructions.

50.00 Cross Walla Walla River, course N.W.

79.70 To post Cor.

Land; broken.

Soil; good on river bottom.

Quite plenty of timber, balm, birch, alder & pine.

N. bet. Secs. 25 & 26.

Var. 21°E.

27.50 Crossed Walla Walla River, course N.W.

40.00 Set $\frac{1}{4}$ Sec. post; made stone mound, & drove charred stake, as per instructions.

80.00 Set post Cor. for Secs. 23, 24, 25 & 26, near summit of hill, facing E. Drove charred stake; dug pits & raised mound, as per instructions.

Land; broken.

Soil; on river bottom, 2nd rate.

Timber; on flat, balm, birch, alder & some pine.