

Subdivisional Lines, T 5 N R 36 E W M.

Chains	E. on random bet. Secs. 24 & 25.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.90	Intersect N. & S. Tp. line, 40 lks. N. of post; from which I run N.89°43'W. on true line.
39.95	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits and raised mound, as per instructions.
79.90	To post Cor. Land; very broken. Grass; poor. Soil; 3rd rate.
	N. bet. Secs. 23 & 24. Var. 21°E.
40.00	Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.
51.25	To N. Fork of Walla Walla River.
80.00	Set post Cor. for Secs. 13, 14, 23 & 24. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Soil; on flat, 1st rate. Some timber; balm, alder, birch and pine.
	E. on random bet. Secs. 13 & 24.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. Tp. line, at post; from which, I run W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post, on side hill, facing S.E. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	To post Cor. Land; very broken. Soil; good 2nd rate. Good grass.