

Subdivisional Lines, T 5 N R 36 E W M.

Chains

N. bet. Secs. 13 & 14.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post on steep hillside, facing last ten chains from summit. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor., near summit on hill, on side facing W. & N., for Secs. 11, 12, 13 & 14. Drove charred stake; dug pits raised mound, as per instructions.

Land; broken.

Grass; good.

Soil; 2nd rate.

E. on random bet. Secs. 12 & 13.

40.00 Set temp. $\frac{1}{4}$ Sec. post.

80.10 Intersect N. & S. T_{pm}eline, 40 lks. S. of post; from which, I run

S. 89° 37' W. on true line.

40.05 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.10 To post Cor.

Land; rolling.

Grass; good.

Soil; 2nd rate.

N. bet. Secs. 11 & 12.

Var. 21° E.

40.00 Set $\frac{1}{4}$ Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

80.00 Set post Cor. for Secs. 1, 2, 11 & 12, S. of ravine, near foot of hill, sloping to N. Drove charred stake; dug pits & raised mound, as per instructions.

Land; rolling.

Grass; good.

Soil; 2nd rate.