

## Subdivisional Lines, T 5 N R 36 E W M.

Chains	E. on random bet. Secs. 1 & 12.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.90	Intersect N. & S. Tp. line, 60 lks. S. of post; from which I run S. 89°34' W. on true line.
39.95	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.90	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
	May 15th, 1865.
	N. on random bet. Secs. 1 & 2. Var. 21° E.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.60	Intersect N. & S. Tp. line, 50 lks. W. of post; from which I run S. 22' W. on true line.
39.60	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
79.60	To post Cor. Land; broken. Grass; good. Soil; 2nd rate.
	N. bet. Secs. 34 & 35. Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor., for Secs. 26, 27, 34 & 35. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; good. Soil; 2nd rate.