

Subdivisional Lines, T 5 N R 36 E W M.

Chains	
48.80	S. branch of Walla Walla.
52.35	N. " " " "
62.00	Foot of hill.
80.00	Set post Cor. for Secs. 15, 16, 21 & 22, on hill side, facing W. Drove charred stake; dug pits & raised mound, as per instructions.
	Some timber along river; alder, birch, balsam & maple under undergrowth
	Soil; in bottom, 1st rate.
	E. on random bet. Secs. 15 & 22.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
80.00	Intersect N. & S. line, 30 lks. S. of post; from which I run
	S. $89^{\circ}47'$ W. on true line.
40.00	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.
52.50	Road, course N.
80.00	To post Cor.
	Land; broken.
	Grass; good.
	Soil; 2nd rate.
	N. bet. Secs. 15 & 16.
	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post, on side hill, facing W.
52.50	To trail, course N.W.
80.00	Set post Cor. for Secs. 9, 10, 15 & 16, on S. side of round Butte. Drove charred stake; dug pits & raised mound, as per instructions.
	Land; broken.
	Grass; good.
	Soil; 2nd rate.
	May 17th, 1865.