

Subdivisional Lines, T 5 N R 36 E W M.

Chains	
39.88	Set $\frac{1}{4}$ Sec. post, land facing to E. Drove charred stake; dug pits & raised mound, as per instructions.
79.76	To post Cor. Land; broken. Grass; good. Soil; 2nd rate.
May 18th, 1865.	
N. bet. Secs. 16 & 17.	
Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post; on land descending to S.W.
80.00	Set post Cor. for Secs. 9, 10, 16 & 17. Drove charred stake; dug pits & raised mound, as per instructions. Land; broken. Grass; good. Soil; 2nd rate.
E. on random bet. Secs. 9 & 16.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.83	Intersect N. & S. line, 24 lks. N. of post; from which, I run N. 89° 50' W. on true line.
39.91	Set $\frac{1}{4}$ Sec. post on hillside, sloping to W. Drove charred stake; dug pits & raised mound, as per instructions.
79.83	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
N. bet. Secs. 8 & 9.	
Var. 21° E.	
40.00	Set $\frac{1}{4}$ Sec. post E. side of ravine, course N.W. Drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 4, 5, 8 & 9, on land sloping N. Drove charred stake; dug pits & raised mound, as per