

Subdivisional Lines, T 5 N R 36 E W M.

Chains		#
	tree, 9.93, thence S. to river 4.67.	
71.26	N. bank of Walla Walla River, about 200 lks. wide, course N.W.	
80.00	Set post Cor. for Secs. 17, 18, 19 & 20. Deposited marked stone; dug pits & raised mound, as per instructions. Land; on river bottom, 1st rate. Timber; birch, balm & alder.	
		#
	E. on random bet. Secs. 17 & 20.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.78	Intersect N. & S. line at post; from which, I run W. on true line.	
31.30	Leave field, course N.W.	
39.89	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised mound, as per instructions.	
79.78	To post Cor. Land; broken. Grass; good. Soil; 2nd rate.	
		#
	W. on random bet. Secs. 18 & 19.	
40.00	Set temp. $\frac{1}{4}$ Sec. post.	
79.63	Intersect N. & S. Tp. line, 20 lks. N. of post; from which I run N. 89° 51' E.	
4.00	To Chouse Creek, 30 lks. wide, course N.	
39.63	Set $\frac{1}{4}$ Sec. post, on steep hillside, facing N.E. Drove charred stake; dug pits & raised mound, as per instructions.	
79.63	To post Cor. Land; rolling. Land on river bottom, 1st rate soil. Good timber for rails & fire wood.	