

Subdivisional Lines, T 5 N R 36 E W M.

Chains	
72.50	Road, course N.W.
79.18	To post Cor. Land; river flat, 1st rate. Timber; balm, birch & alder.
	May 20th, 1865.
	N. bet. Secs. 7 & 8. Var. 20° E.
40.00	Set $\frac{1}{4}$ Sec. post on level; drove charred stake; dug pits & raised mound, as per instructions.
80.00	Set post Cor. for Secs. 5, 6, 7 & 8. Land; gently descending. Drove charred stake; dug pits & raised mound, as per instructions. This line passes over land descending to N. Grass; good. Soil; 2nd rate.
	El on random line bet. Secs. 5 & 8.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.92	Intersect N. & S. Tpweline, 26 lks. S. of post; from which I run S. 89° 49' W. on true line.
39.96	Set $\frac{1}{4}$ Sec. post on land gently sloping. Drove charred stake; dug pits & raised mound, as per instructions.
79.92	To post Cor. Land; rolling. Grass; good. Soil; 2nd rate.
	W. on random bet. Secs. 6 & 7.
40.00	Set temp. $\frac{1}{4}$ Sec. post.
79.60	Intersect N. & S. Tp. line, 66 lks. S. of post; from which I run S. 89° 32' E. on true line.
39.60	Set $\frac{1}{4}$ Sec. post; drove charred stake; dug pits & raised