

Subdivisional Lines, T 5 N R 37 E W M.

Chains	
.25	Leave meadows.
40.17	Set post for $\frac{1}{4}$ Sec. Cor.
53.67	Cross creek.
64.67	Cross creek.
72.00	Cross creek, same at 53.67.
80.35	The Cor. for Secs. 1, 2, 11 & 12. Land; rolling.
<hr/>	
	N. on random line bet. Secs. 1 & 2. Var. 20°E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.60	Intersect Bdy. of Tp., 40 lks. W. of Cor. for Secs. 1, 2, 35 & 36; from this Cor., I run S.19' W. on true line bet. Secs. 1 & 2.
23.60	Enter swampy opening.
32.60	Cross spr. branch, leave swamp.
40.60	Set post for $\frac{1}{4}$ Sec. Cor.; from which A willow, 5 ins. diam., brs. N.18°W., 31 lks. dist. A fir, 13 ins. diam., brs. S.14°E., 42 lks. dist.
80.60	The Cor. for Secs. 1, 2, 11 & 12. Land; rolling. Timber; tamarack, pine & fir. Oct. 31, 1872.
<hr/>	
	N. bet. Secs. 34 & 35. Var. 21°E.
21.00	Leave timber; descend.
40.00	Set stone, 12 x 15 x 18, for $\frac{1}{4}$ Sec. Cor., mound stone.
52.00	Enter timber.
71.00	Ridge falls W., 700 ft.
80.00	Set post for Cor. to Secs. 26, 27, 34 & 35; from which A pine, 11 ins. diam., brs. N.18°E., 34 lks. dist. A " 14 " " " N.27°W., 113 lks. dist. A fir, 9 " " " S.32°W., 115 " " A pine, 7 " " " S.48°E., 41 " "