

Subdivisional Lines, T 5 N R 37 E W M.

Chains

17.00 Road to timber.

40.00 Set post & stone, on hillside, for $\frac{1}{4}$ Sec. Cor.

80.00 Set post & stone, for Cor. to Secs. 4, 5, 8 & 9.
Land; mountainous.
Good grass.

E. on random line bet. Secs. 4 & 9.

40.00 Set post for temp. $\frac{1}{4}$ Sec. Cor.

79.86 Intersect N. & S. line, 47 lks. S. of Cor. for Secs. 3, 4,
9 & 10; from this Cor., I run
N.89°40' W. on true line bet. Secs. 4 & 9.

39.90 Set post & stone, mound & pits, for $\frac{1}{4}$ Sec. Cor.

58.30 Road, N.W. to timber.

61.00 Spr. Cr., 20 lks. wide; ascend.

79.80 The Cor. for Secs. 4, 5, 8 & 9.
Land; hilly.
Good grass.

N. on random line bet. Secs. 4 & 5.
Var. 20 $\frac{1}{2}$ ° E.

40.00 Set post for temp. $\frac{1}{4}$ Sec. Cor.

80.46 Intersect N. Bdy. of Tp., 84 lks. W. from Cor. to Secs.
4, 5, 32 & 33; from which Cor., I run
S.36' W. on true line bet. Secs. 4 & 5.

2.00 Road to timber.

4.00 Spr. branch, 15 lks. wide.

40.40 Set post & stone, mound & pits, for $\frac{1}{4}$ Sec. Cor.

80.40 The Cor. for Secs. 4, 5, 8 & 9.
Land; mountainous.
No timber.
Good grass.

Nov. 8th, 1872.

N. bet. Secs. 31 & 32.

Var. 21° E.