

Subdivisional Lines, T 5 N R 37 E W M.

Chains	
8.59	Foot of hill; Walla Walla, S. Fork, 80 lks. wide, N.W.
11.84	Wagon road to Burns sawmill; ascend.
40.00	Set stone, 12 x 15 x 15, for $\frac{1}{4}$ Sec. Cor.
80.00	Set stone, 3 x 12 x 20, for Cor. to Secs. 29, 30, 31 & 32, (mound & pits.)
	Land; hills.
	Birch & alder along river.
<hr/>	
	E. on random bet. Secs. 29 & 32.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
79.80	Intersect N. & S. line, 48 lks. S. of Cor. for Secs. 28, 29, 32 & 33; from this Cor., I run
	S. 89°39' W. on true line bet. Secs. 29 & 32.
39.90	Set post & stone for $\frac{1}{4}$ Sec. Cor.
79.80	The Cor. for Secs. 29, 30, 31 & 32.
	Land; hills.
	Good grass.
<hr/>	
	W. on random line bet. Secs. 30 & 31.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.27	Intersect W. Bdy. of Tp., 59 lks. N. of Cor. for Secs. 25, 30, 31 & 36; from this Cor., I run
	N. 89°35' E. on true line bet. Secs. 30 & 31.
40.27	Set post & stone for $\frac{1}{4}$ Sec. Cor.
45.77	Spr. branch, 3 lks. wide, S. 10° W.
80.27	The Cor. for Secs. 29, 30, 31 & 32.
	Land; hilly.
	Good grass.
<hr/>	
	N. bet. Secs. 29 & 30.
	Var. 21° E.
36.00	Summit of Divide bet. N. & S. Fork of Walla Walla River; Descend.
40.00	Set stone, 8 x 13 x 19, for $\frac{1}{4}$ Sec. Cor.
61.78	Foot of bluff; ascend road.