

Subdivisional Lines, T 5 N R 37 E W M.

Chains

67.70 N. Fork of Walla Walla River, 60 lks. wide.
 68.70 Foot of bluff; ascend.
 80.00 Set stone, 8 x 15 x 24, for Cor. to Secs. 19, 20, 29 & 30.
 Land; 2nd rate.
 Good grass.

E. on random line bet. Secs. 20 & 29.

40.00 Set stone for temp. $\frac{1}{4}$ Sec. Cor.
 80.78 Intersect N. & S. line, 37 lks. W. of Cor. for Secs. 20, 21,
 28 & 29; from which Cor., I run
 N. 89° 44' W. on true line bet. Secs. 20 & 29.
 40.39 Set post & stone, for $\frac{1}{4}$ Sec. Cor.; descend hill.
 80.78 The Cor. for Secs. 19, 20, 29 & 30.
 Land; hilly.
 Good grass.

Nov. 9th, 1872.

A severe snow storm lasting until the 16th, layed by to
 December 1872.

W. on random line bet. Secs. 19 & 30.

40.00 Set post for temp. $\frac{1}{4}$ Sec. Cor.
 80.60 Intersect W. Bdy. at post for Cor. of Secs. 19, 24, 25 &
 30; from which Cor., I run
 E. on true line bet. Secs. 19 & 30.
 31.10 Enter bottom.
 36.10 Road N.W.
 40.60 Set post & marked staone, for $\frac{1}{4}$ Sec. Cor.
 44.00 Leave ploughed ground of Mr. Jones; enter timber.
 46.50 Cross river, N. Fork of Walla Walla.
 53.00 Recross river.
 55.50 Recross river.
 58.00 Leave bottom and ascend.
 80.60 The Cor. of Secs. 19, 20, 29 & 30.
 Land; hilly. Timber; birch & cottonwood.
 Mr. Jones is settled in S.W $\frac{1}{4}$ of Sec. 19.