

Subdivisional Lines, T 5 N R 37 E W M.

Chains	
40.00	Set stone, 6 x 6 x 12, for $\frac{1}{4}$ Sec. Cor.
52.20	Road, N.E.
55.00	Ridge.
58.50	Road, E. & W.; descend.
80.00	Set stone, 5 x 8 x 10, for Cor. to Secs. 7, 8, 17 & 18. Land; rolling hills. Soil; good.
	E. on random line bet. Secs. 8 & 17.
40.00	Set stone for temp. $\frac{1}{4}$ Sec. Cor.
79.60	The Cor. for Secs. 8, 9, 16 & 17; from which Cor., I run W. on true line bet. Secs. 8 & 17.
23.10	Leave timber; cross fence.
35.70	Leave field; cross fence.
39.80	Set post & stone, for $\frac{1}{4}$ Sec. Cor.
46.60	Road, N. & S.
55.00	Bottom of ravine.
61.00	Road to timber.
79.60	The Cor. for Secs. 7, 8, 17 & 18. Good soil. Bunch grass good.
	W. on random line bet. Secs. 7 & 18.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.42	Intersect W. Bdy. of Tp., 51 lks. N. of Cor. for Secs. 7, 12, 13 & 18; from which Cor., I run N.89°38' E. on true line bet. Secs. 7 & 18.
19.42	Road, N.E. & S.W.
42.42	Set post & stone, for $\frac{1}{4}$ Sec. Cor.
59.42	Cross N.W.
80.42	The Cor. for Secs. 7, 8, 17 & 18. Soil; 2nd rate, rolling. Good grass.