

Subdivisional Lines, T 5 N R 37 E W M.

Chains	N. bet. Secs. 7 & 8.	Var. 21° E.
3.00	Road, E. & W.	
5.00	Bottom of gulch; ascend.	
16.50	Road, N.W.	
17.00	Ridge; descend.	
34.50	Ravine.	
40.00	Set post & stone for $\frac{1}{4}$ Sec. Cor.	
48.52	Cross ridge.	
60.96	Cross gulch.	
80.00	Set stone, 20 x 24 x 30, for Cor. to Secs. 5, 6, 7 & 8.	
	Land; hilly.	
	Good grass.	
	E. on random line bet. Secs. 5 & 8.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.72	Intersect N. & S. line, 41 lks. N. of Cor. for Secs. 4, 5, 8 & 9; from which Cor., I run	
	N. 89° 41' W. on true line bet. Secs. 5 & 8.	
9.72	Ridge, 400 ft., falls N.W.	
16.72	Road, N.E.	
39.86	Set post & stone, for $\frac{1}{4}$ Sec. Cor.; descend.	
79.72	The Cor. for Secs. 5, 6, 7 & 8.	
	Land; hilly, 2nd rate.	
	Good grass.	
		Dec. 17th, 1872.
	W. on random line bet. Secs. 6 & 7.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.30	The Cor. for Secs. 1, 6, 7 & 12; from which Cor., I run	
	E. on true line bet. Secs. 6 & 7.	
5.00	Bottom of gulch.	
22.30	Road, N. & S.	
40.30	Set post for $\frac{1}{4}$ Sec. Cor.	
45.30	Bottom of gulch.	
80.30	The Cor. for Secs. 5, 6, 7 & 8.	
	Land; 2nd rate. Good grass.	