

South Bdy., T 6 N R, 37 E W M.

Chains	E. on S. Bdy. of Sec. 32.	Var. 21° E.
15.00	Road, course N.W.	
40.00	Set $\frac{1}{4}$ Sec. post, on W. side of ravine, course N.E. Drove charred stake; dug pits & raised mound, as per instructions.	
76.38	A fir, 12 ins. diam., brs. N. 20 lks.	
76.60	A creek, 10 lks. wide, course N.W.	
80.00	Set post Cor. for Secs. 32 & 33, 4 & 5, on side hill, facing W. Drove charred stake; dug pits & raised mound, as per instructions.	
	Land; broken.	
	Good grass.	
	Soil; 2nd rate.	
	E. on S. Bdy. of Sec. 33.	Var. 21° E.
40.00	Set $\frac{1}{4}$ Sec. post, on side hill, facing S. Made Cor. of basalt stone, 14 x 12 x 4.	
48.25	Two fir trees, brs. S., about 500. The only trees in the ravine.	
80.00	Set post Cor. for Secs. 33, 34, 3 & 4, on steep hillside, facing S.W. Made mound of stone, as per instructions.	
	Land; broken.	
	Good grass.	
	Soil; good 2nd rate.	
	E. on S. Bdy. of Secs. 34.	Var. 21° E.
28.60	Spring branch, 2 lks. wide, course N.W.	
40.00	Set $\frac{1}{4}$ Sec. post, on steep hillside, facing W.	
80.00	Set stone, 14 x 10 x 8, basalt Cor. for Secs. 34, 35, 2 & 3 on steep hillside, facing E.	
	This line passes over spurs of mountains coursing to N.E. very broken, some scattering timber in ravine.	