

South Bdy., T 6 N R 37 E W M.

Chains

E. bet. Secs. 2 & 35, Tps. 5 & 6 N., R. 37 E.

Var. 21°E.

12.38 Creek, 10 lks. wide, course N.W.

40.00 Set post Cor. for $\frac{1}{4}$ Sec., in small grove of timber, on mountain side, facing N.; from which

A willow, 5 ins. diam., brs. S. 24° lks.

A fir, 10 ins. diam., brs. N. 84° E., 31 lks.

48.25 Enter timber.

80.00 Set post Cor. for Secs. 1, 2, 35 & 36; from which

A larch, 18 ins. diam., brs. N. 49° W., 8 lks.

A " 18 " " " S. 53° W., 32 "

A " 20 " " " S. 12° E., 30 "

A " 20 " " " N. 54° E., 34 "

This line passes up steep mountain side.

Timber; excellent fir & larch.

Undergrowth; same & yew, willow & maple.

E. on S. Bdy. of Sec. 36.

Var. 21°E.

40.00 Set $\frac{1}{4}$ Sec. post Cor.; from which

A fir, 20 ins. diam., brs. S. 54° E., 20 lks.

A willow, 5 ins. diam., brs. N. 9° W., 30 lks.

80.00 Set post Cor. for Tps. 5 & 6 N., Rs. 37 & 38 E.; from which

A fir, 20 ins. diam., brs. N. 7° W., 23 lks.

A " 20 " " " N. 18° E., 22 lks.

A " 20 " " " S. 40° E., 18 lks.

A " 10 " " " S. 23° W., 24 lks.

This line passes through excellent timber.

Land; gently rolling.

Soil; good

Timber; fir, larch & pine.

Undergrowth; same and maple & yew.