

Exterior Lines, T 5 N R 39 E W M.

Chains	
	<p>N. bet. Secs. 19 & 24.</p> <p style="text-align: right;">Var. 21° E.</p>
11.75	<p>Top of ridge brs. N.E. & S.W., 500 ft. above Sec. Cor., impossible to chain. Send flag ahead to point on line and run a Base, 400 lks.W., gives an angle of 5°15', Base multiplied by Nat. Cotan. of angle gives 4352 lks. to flag plus 1175 lks. gives</p>
55.27	<p>To flag from last Sec. Cor.</p> <p>Impracticable to set the $\frac{1}{2}$ Cor. bet. Secs. 19 & 24, on account of rough and broken ground.</p>
59.00	<p>Top of high ridge brs. N.W. & S.E., 500 ft. above top of last ridge; and</p> <p>Descend.</p>
63.25	<p>Ravine, course E., 100 ft. below top of ridge and</p> <p>Ascend.</p>
66.50	<p>Top to ridge brs. E. & W., 100 ft. above last ravine.</p>
68.10	<p>Ravine, course E., 100 ft. below top of last ridge and</p> <p>Ascend.</p>
74.25	<p>Top of ridge brs. E. & W., 100 ft. above last ravine and</p> <p>Descend.</p>
78.50	<p>Ravine, course E., 75 ft. below top of last ridge.</p>
80.00	<p>Set basalt stone, 18 x 10 x 10 ins., 12 ins. in ground, for Cor. to Secs. 18, 19, 13 & 24, 30 ft. above last ravine, marked with 3 notches on N. & S. edges; from which</p> <p style="padding-left: 40px;">A hemlock, 48 ins. diam., brs. S. 25° E., 32 lks. dist.,</p> <p style="padding-left: 40px;">marked T 5 N R 39 E S 19 B T.</p> <p>And raised mound of stone alongside. Pits impracticable.</p> <p>Land; mountainous.</p> <p>Soil; 4th rate.</p> <p>Timber; hemlock, fir, spruce and pine and</p> <p>Some undergrowth of fir, spruce & pine.</p> <p style="text-align: right;">Aug. 4th, 1882.</p>
	<p>N. bet. Secs. 13 & 18.</p> <p style="text-align: right;">Var. 22° E.</p>
25.75	<p>Top of ridge brs. E. & W., 400 ft. above Sec. Cor.</p>