

## Resurvey E. Bdy. T 5 N R 38 E W M.

| Chains |   |
|--------|---|
|        | <p>July 20:</p> <p>From the Cor. of Secs. 25, 30, 31 &amp; 36, I run<br/>N. bet. Secs. 25 &amp; 30.</p> <p>Ascending over steep, stony ridge; brs. E. &amp; W.</p>  |
| 7.00   | Top of ridge; descend through timber; trail on ridge.   |
| 40.00  | <p>Falls on a rock in place, 6 x 4 x 4 ins., above ground, on<br/>which, I cut a cross (X) at exact point for <math>\frac{1}{4}</math> Sec. Cor.,<br/>marked <math>\frac{1}{4}</math> on W. face; from which</p> <p style="padding-left: 40px;">A fir, 10 ins. diam., brs. S.70°E., 38 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S 30 B T.</p> <p style="padding-left: 40px;">A fir, 12 ins. diam., brs. N.70°W., 88 lks. dist.,<br/>marked <math>\frac{1}{4}</math> S 25 B T.</p> <p>From this Cor., the old <math>\frac{1}{4}</math> Sec. Cor., a basalt stone, 18 x 14<br/>x 4 ins., marked &amp; witnessed as described by the Sur-<br/>veyor General, brs. N., 1 ch., 88 lks. dist.; I destroy<br/>all traces of this old Cor.</p> |
| 66.63  | <p>Bottom of canyon, 800 ft. deep; branch, 15 lks. wide, runs<br/>S.E.- tributary to the S. Fork of Walla Walla river.</p> <p>Ascend steep, bluff hill, through scattering timber.</p>  |
| 80.00  | <p>A point, 600 ft. below Sec. Cor. and set a basalt stone, 15 x 8 x 6 ins., 10 ins. in ground, for Cor. to Secs.<br/>19, 24, 25 &amp; 30, marked with 4 notches on N. and 2 not-<br/>ches on S. edges; and raised mound of stone, 2 ft. base,<br/><math>1\frac{1}{2}</math> ft. high, W. of Cor. Pits impracticable.</p> <p>From this Cor., the remains of the old Sec. Cor., a broken<br/>basalt stone, with mound of stone, brs. N. 2 chs., 30<br/>lks. dist. I destroy all traces of this old Cor.</p> <p>Land; mountainous.</p> <p>Soil; stony, 4th rate.</p> <p>Timber; scattering pine &amp; fir.</p> <p>Undergrowth; chaparral, pine, fir, huckleberry, willow &amp;<br/>bunch grass.</p> <p>Mountainous land, 80 chs.</p>            |