

## Dependent Resurvey E. Bdy., T 5 N R 38 E W M.

## Chains

Timber; fir, pine, spruce & tamarack.  
Undergrowth; alder, vinemaple, laurel, huckleberry, willow,  
syringa, mountain ash, fern and Oregon grape.

N.0°29'W., on true line on E. Bdy. of Sec. 1.

Asc. 84 ft. over SW. slope, through heavy timber & dense undergrowth.

4.60 Rocky spur, slopes W.; desc. 75 ft. over NW. slope.

8.70 Spring branch, 1 lk. wide, course W.; asc. 199 ft. over SW. slope.

20.00 Spur, slopes W.; desc. 491 ft. over NW. slope.

39.83 Proportionate point for  $\frac{1}{4}$  Sec. Cor. of Sec. 1 only.

Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for  $\frac{1}{4}$  Sec. Cor. of Sec. 1 only, with brass cap, marked

$\frac{1}{4}$  S 1 |  
1935

from which

A fir, 26 ins. diam., brs. S.49°W., 96 lks. dist., marked  $\frac{1}{4}$  S 1 B T.

A fir, 14 ins. diam., brs. N.51°W., 66 lks. dist., marked  $\frac{1}{4}$  S 1 B T.

Continue to desc. 170 ft. over NW. slope.

43.40 Creek, 3 lks. wide, course N.70°W.; asc. 42 ft. over SW. slope.

46.60 Spur, slopes W.; desc. 130 ft. over NW. slope.

56.60 Ravine, course S.20°W.; asc. 586 ft. over SE. slope.

70.50 Road, from Walla Walla to Skyline, brs. NE. & SW.

85.84 Trail, brs. E & W.

87.50 Spur, slopes E.; desc. 18 ft. over NE. slope.

93.08 The Closing Cor. of Tps. 5 N Rs 38 & 39 E on S. Bdy. of Sec. 36, T 6 N R 38 E, which is a post, 4 ins. sq., 30 ins. above ground, marked

T 5 N C C on S.  
R 39 E S 6 on E., and  
R 38 E S 1 on W.

At point for Cor.

Set an iron post, 3 ft. long, 3 ins. diam., 27 ins. in the ground, for Closing Cor. to Tps. 5 N., Rs. 38 & 39 E., with brass cap, marked