

Subdivisional Lines, T 5 N R 38 E W M.

Chains	
	<p>Undergrowth; chaparral, fir, spruce, tamarack, pine, alder, willow, huckleberry and bunch grass.</p> <p>Mountainous land; 80.10 chs.</p>
	<p>N.0°2'W. bet. Secs. 26 & 27.</p> <p>Descend steep hill through heavy timber; brs. N.30°W. and S.30°E.</p>
18.75	Stream, 5 lks..wide, runs S.70°E.; steep ascent.
24.25	A fir, 20 ins. diam., on line, I mark with 2 notches on N. and S. sides.
34.50	Descend; hill brs. N.50°W. and S.50°E.
38.00	Stream, 3 lks. wide, runs E.; ascend.
40.00	<p>A point, 100 ft. above Sec. Cor. and</p> <p>Set basalt stone, 18 x 10 x 6 ins., 13½ ins. in ground, for ¼ Sec. Cor., marked ¼ on W. face; from which</p> <p>A fir, 18 ins. diam., brs. N.27°E., 53 lks. dist., marked ¼ S 26 B T.</p> <p>A fir, 15 ins. diam., brs. S.30°W., 35 lks. dist., marked ¼ S 27 B T.</p>
41.00	Thence through scattering timber.
47.50	Belt of heavy timber; brs. N.20°W. and S.20°E.
56.98	Ascend ravine,
64.00	Leave ravine, N.40°E.
65.00	Hill brs. N.60°E. and S.60°W.; thence through scattering timber.
80.00	<p>A point, 1100 ft. above Sec. Cor. S. and</p> <p>Set basalt stone, 20 x 15 x 10 ins., 15 ins. in ground, for Cor. of Secs. 22, 23, 26 & 27, marked with 2 notches on S. and E. edges; from which</p> <p>A fir, 15 ins. diam., brs. N.77½°E., 98 lks. dist., marked T 5 N R 38 E S 23 B T.</p> <p>A fir, 20 ins. diam., brs. S.48°E., 34 lks. dist., marked T 5 N R 38 E S 26 B T.</p> <p>A pine, 28 ins. diam., brs. S.80°W., 2 chs. & 19 lks. dist marked T 5 N R 38 E S 27 B T.</p>