

Subdivisional Lines, T 5 N R 38 E W M.

Chains.	
80.06	Intersect N. & S. line, 9 lks. N. of Cor. of Secs. 2, 3, 10 & 11.
	Thence I run
	W. on true line bet. Secs. 3 & 10.
	Ascending from N. border of river bottom, through heavy timber timber and undergrowth.
	Hill brs. N.15°E. and S.15°W.
10.00	Steeper ascent through smaller timber and undergrowth.
15.50	Top of rocky point, brs. S.30°E.
	Descend.
21.80	Ravine, 50 ft. deep, course S.E.
	Ascend steep hill through heavy timber and undergrowth.
30.75	Top of rise on narrow ridge, brs. N. & S.
	Descend steep hill, same bearing.
40.03	Set an iron stone, 20 x 8 x 8 ins., 15 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; from which A fir, 18 ins. diam., brs. N.40°E., 46 lks. dist., marked $\frac{1}{4}$ S 3 B T. A fir, 18 ins. diam., brs. S.67°W., 80 lks. dist., marked $\frac{1}{4}$ S 10 B T.
44.75	Foot of hill.
	Stream, 3 lks. wide, runs S.
	Ascend.
46.00	Branch trail from river to divide N.
57.50	Top of rise; descend S. slope.
68.23	Foot of descent.
	Stream, 2 lks. wide, runs S.30°E.
75.00	Leave timber, brs. N.40°W. and S.40°E.
76.75	Top of rise on spur, brs. N.60°W. and S.60°E.
79.50	Enter timber, brs. N.30°W. and S.30°E.
80.06	A point, 150 ft. above Sec. Cor. E. and the Cor. of Secs. 3, 4, 9 & 10.
	Land; mountainous. Soil; gravelly & stony, 2nd, 3rd & 4th rates. Timber; fir, tamarack, pine & spruce. Undergrowth; chaparral, fir, tamarack, pine, spruce, alder, willow, huckleberry & bunch grass. Mountainous land; 80.06 chs.