

## Subdivisional Lines, T 5 N R 38 E W M.

Chains	
80.20	Intersect N. & S. line, 28 lks. N. of Cor. of Secs. 27, 28, 33 & 34. Thence I run N.89° 45'W. on true line bet. Secs. 28 & 33. Descending S. side of hollow through heavy timber.
15.00	Branch, 6 lks. wide, runs S.80°W., thence descend N. side of hollow.
16.00	South point of rock ledge.
20.25	Cross moraine, 50 lks. wide, steep slope S.
24.00	Down bluffs, brs. N.W.
40.10	A point, 600 ft. below Sec. Cor. and Set basalt stone, 20 x 18 x 6 ins., 10 ins. in ground, ( strike rock and place mound of stones, firmly about Cor.), for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face; from which A fir, 12 ins. diam., brs. S.50°E., 46 lks. dist., marked $\frac{1}{4}$ S 33 B T. A fir, 7 ins. diam., brs. N.63°W., 7 lks. dist., marked $\frac{1}{4}$ S 28 B T.
40.35	Small spring, course S.
53.50	Same branch, before noted at 15.00 chs., 10 lks. wide, runs N.80°W., thence along S. side of deep hollow, over fall- en poles and through dense undergrowth.
65.00	Enter scattering timber.
80.20	A point, 700 ft. below $\frac{1}{4}$ Sec. Cor. and the Cor. of Secs. 28, 29, 32 & 33. Land; rolling, hilly & mountainous. Soil; part arable, sandy alluvial, gravel & stone, 2nd, 3rd and 4th rates. Heavily timbered with fir, larch, pine, tamarack and spruce, 65.00 chs. Densely overgrown with fir, larch, pine, tamarack, spruce, huckleberry, thimbleberry, cascara, alder, willow and bunchgrass, 26.70 chs. Mountainous, heavily timbered or lands densely covered with undergrowth; 80.20 chs.

August 5, 1899.