

Subdivisional Lines, T 5 N R 38 E W M.

Chains

- 56.75 Bottom of ravine, 400 ft. deep, course S.80°E.  
Ascend.  
Hill brs. N.70°E. and S.70°W.
- 63.00 Top of point, brs. E. & W.  
Descend.
- 73.25 Foot. Dry bed of stream, 10 lks. wide, course S.50°E.  
Ascend.
- 75.75 A fir, 28 ins. diam., on line, 1 mark with 2 notches on N.  
and S. sides.
- 80.00 A point, 600 ft. above  $\frac{1}{4}$  Sec. Cor. and  
Set an ironstone, 30 x 24 x 20 ins., 15 ins. in ground,  
( strike rock and place mound of stone firmly about  
Cor. ), for Cor. of Secs. 16, 17, 20 & 21, marked with  
3 notches on S. and 4 notches on E. edges; from which  
A pine, 40 ins. diam., brs. N.76°E., 77 lks. dist.,  
marked T 5 N R 38 E S 16 B T.  
A pine, 30 ins. diam., brs. S.63°E., 73 lks. dist.,  
marked T 5 N R 38 E S 21 B T.  
A pine, 30 ins. diam., brs. S.72°W., 1 ch, 75 lks. dist.,  
marked T 5 N R 38 E S 20 B T.  
A pine, 30 ins. diam., brs. N.24°W., 1 ch., 45 lks. dist.,  
marked T 5 N R 38 E S 17 B T.
- Land; level, hilly and mountainous.  
Soil; part arable, sandy loam, gravel and stone, 2nd, 3rd  
and 4th rates.  
Heavily timbered with pine, fir, tamarack and spruce, 50.00  
chs.  
Undergrowth; chaparral, pine, fir, tamarack, spruce, alder,  
willow, huckleberry, cascara, fern & bunch grass.  
Mountainous, or heavily timbered lands, 80.00 chs.
- 
- S.89° 45' E. on random line bet. Secs. 16 & 21.
- 40.00 Set temp.  $\frac{1}{4}$  Sec. Cor..
- 80.00 Intersect N. & S. line, 6 lks. S. of Cor. of Secs. 15, 16,  
21 & 22.