

## Subdivisional Lines, T 5 N R 38 E W M.

Chains	<p>marked <math>\frac{1}{4}</math> S 29 B T.</p> <p>A fir, 20 ins. diam., brs. N.78<math>\frac{1}{2}</math>° W., 35 lks. dist., marked <math>\frac{1}{4}</math> S 30 B T.</p> <p>62.50 Blazed trail, brs. N.50°W. &amp; S.50°E.</p> <p>64.50 Foot of hill.</p> <p>N. Fork of Walla Walla River, 30 lks. wide, flows N.50°W. Cross bottom.</p> <p>66.00 Ascend steep hill, brs. E. &amp; W.</p> <p>68.75 Ridge, brs. N.70°E.</p> <p>Enter deadened timber.</p> <p>71.75 Ravine, course S.60°W.</p> <p>80.00 A point, 150 ft. above <math>\frac{1}{4}</math> Sec. Cor. and Set basalt stone, 18 x 10 x 6 ins., 13<math>\frac{1}{2}</math> ins. in ground, for Cor. of Secs. 19, 20, 29 &amp; 30, marked with 2 notches on S. and 5 notches on E. edges. Raised mound of stone, 2 ft. base, 1<math>\frac{1}{2}</math> ft. high, W. of Cor. Pits impracticable. Land; mountainous, &amp; level. Soil; part arable, sandy loam, gravel &amp; stone, 2nd, 3rd &amp; 4th rates. Heavily timbered with fir, tamarack, spruce and pine, 68.75 chains. Undergrowth; chaparral, fir, tamarack, spruce, pine, alder, huckleberry, willow &amp; bunchgrass. Mountainous, or heavily timbered land, 80.00 chs.</p>
	<p>By Deputy Wm. E. Campbell.</p> <p>N.89°52'E. on random line bet. Secs. 20 &amp; 29.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> Sec. Cor.</p> <p>80.22 Intersect N. &amp; S. line, 14 lks. N. of Cor. of Secs. 20, 21, 28 &amp; 29.</p> <p>August 7: Thence I run S.89°58' W. on true line bet. Secs. 20 &amp; 29. Descending through deadened timber. Hill brs. N.E. &amp; S.W.</p>