

Exterior Lines, T 5 N R 39 E W M.,
As surveyed by Rufus S. Moore, U.S. Deputy Surveyor,
Under Contract No. 437,
Dated June 3, 1882.

Chains

From the Cor. to Tps. 5 & 6 N Rs. 38 & 39 E., which is a
post, 4 ins. sq., marked

T 6 N S 31 on N.E.

R 38 E S 36 on N.W.

T 5 N S 1 on S.W. and

R 39 E S 6 on S.E. faces, with

6 notches on N., S., E. & W. edges

with mound of earth, pits, etc. Destroyed marks referring
to Sec. 1 and run

S. 89° 44' E. on true line bet. Secs. 6 & 31.

Var. 22° E.

Ascend along hillside to

13.25 Top of divide and old Indian Trail, brs. N.E. & S.W., 400
ft. above Cor.

17.59 Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for
Cor. to Secs. 5, 6, 31 & 32, marked

T 6 N S 32 on N.E.

R 39 E S 31 on N.W.

T 5 N S 6 on S.W. &

S 5 on S.E. faces, with

5 notches on E. &

1 notch on W. edges,

from which

A spruce, 20 ins. diam., brs. S. 52° W., 7 lks. dist.,
marked T 5 N R 39 E S 6 B T.

A spruce, 18 ins. diam., brs. S. 71° E., 46 lks. dist.,
marked T 5 N R 39 E S 5 B T.

A spruce, 20 ins. diam., brs. N. 40° E., 18 lks. dist.,
marked T 6 N R 39 E S 32 B T.

A tamarack, 20 ins. diam., brs. N. 79° W., 61 lks. dist.,
marked T 6 N R 39 E S 31 B T.

Land; broken and mountainous.

Soil; 3rd & 4th rates.

Heavily timbered with pine, fir & tamarack.

Dense undergrowth of pine & fir.

Aug. 27th, 1883.