

Dependent Resurvey of S. Bdy., of Sec.36, T 6 N R 38 E.

Chains

Continue to asc. 54 ft. over E. slope.

63.02 The Closing Cor. of Tps. 5 N., Rs. 38 & 39 E., heretofore described.

Continue to asc. 176 ft. over E. slope.

81.14 The old Cor. of Secs. 35 & 36, which is a rotted remains of old post, with no marks legible set in an old mound of stone, on ridge, brs. N. & S.

At point for Cor.

Set an iron post, 3 ft. long, 2 ins. diam., 12 ins. in the ground to solid rock and in a mound of stone to top, for Cor. of Secs. 35 & 36, with brass cap, marked

T6N | R38E  
 S35 | S36  
 T5N | R38E  
 S 1  
 1932

from which

A spruce stump, 8 ins. diam., brs. N.2°E., 48 lks. dist., marked B.T., other marks rotted off. (Old B.T.)

A fir, 10 ins. diam., brs. N.42½°E., 110 lks. dist., marked T 6 N R 38 E S 36 B T. (New B.T.)

A fir, 10 ins. diam., brs. N.81°W., 115 lks. dist., marked T 6 N R 38 E S 35 B T. (New B.T.)

Land; mountainous.

Soil; rocky loam, sandy, 3rd rate.

Timber; fir, pine, spruce and tamarack.

Undergrowth; alder, vinemaple, salal, willow, laurel, mountain ash, huckleberry, fern & Oregon grape.

Subdivisional Lines, T 5 N R 39 E W M.

As surveyed by the same U.S. Transitman,

Under the same Special Instructions, and Date.

From the Standard Cor. of Secs. 31 & 32, on S. Bdy. of Tp.

N.0°05'W., bet. Secs. 31 & 32.

Desc. 491 ft. over NW. slope, through heavy second growth timber and dense undergrowth.

14.15 Ravine, course N.70°W.; asc. 508 ft. over SW. slope.

33.95 Spur, slopes N.70°W.; desc. 339 ft. over N. slope.

44.80 Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground for ¼ Sec. Cor., with brass cap, marked

↑  
 S31 | S32  
 1932

from which