

Subdivision of T. 5 N., R. 39 E.,

Chains		Feet												
81.36	Small spur, slopes NE.; continue to asc. 15 ft. over NE. slope.													
87.47	Intersect E. Bdy. of T 5 N., R. 38 E. Set an iron post, 3 ft. long, 2 ins. diam., 16 ins. in the ground to solid rock and in a mound of stone to top, for closing cor. of secs. 30 and 31, with brass cap marked													
	<table border="1"> <tr> <td>T5N</td> <td>T5N</td> <td></td> </tr> <tr> <td>S25</td> <td>S30</td> <td>CC ✓</td> </tr> <tr> <td>R38E</td> <td>S31</td> <td></td> </tr> <tr> <td></td> <td>R39E</td> <td></td> </tr> </table>	T5N	T5N		S25	S30	CC ✓	R38E	S31			R39E		
T5N	T5N													
S25	S30	CC ✓												
R38E	S31													
	R39E													
	1932													
	from which													
	A fir, 26 ins. diam., brs N. 38° E., 46 lks. dist., marked T 5 N R 39 E S 30 C C B T													
	A fir, 12 ins. diam., brs. S. 75° E., 60 lks. dist., marked T 5 N R 39 E S 31 C C B T.													
	From this point the cor. of secs. 25 and 36 only, bears South, 5.57 chs. dist., heretofore described.													
	Land; mountainous. Soil, rocky loam; 3rd rate. Timber, fir, pine, spruce and tamarack. Undergrowth, alder, salal, vinemaple, laurel, huckleberry, thorn, willow, mountain ash and buck brush.													
	To complete the survey of sec. 31, I go to the $\frac{1}{4}$ Sec. cor. of sec. 36 only, on E. bdy. of T 5 N., R. 38 E., and run													
	North, along the E. bdy. of sec. 36.													
4.51	Point 40.00 chs. in southing from closing cor. of secs. 30 and 31. Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for $\frac{1}{4}$ Sec. cor. of sec. 31 only, with brass cap marked													
	<table border="1"> <tr> <td>$\frac{1}{4}$ S 31</td> </tr> </table>	$\frac{1}{4}$ S 31												
$\frac{1}{4}$ S 31														
	1932													
	from which													
	A fir, 6 ins. diam., brs. N. 52° E., 41 lks. dist. marked $\frac{1}{4}$ S 31 B T.													
	A fir, 5 ins. diam., brs. S. 58° E., 22 lks. dist. marked $\frac{1}{4}$ S 31 B T.													
	From the cor. of secs. 29, 30, 31 & 32.													