

Subdivision of T 5 N., R 39 E.

Chains		Feet
	Soil, sandy loam, rocky; 3rd rate. Timber, fir, pine, spruce and tamarack. Undergrowth, alder, huckleberry, vinemaple, laurel, rose, willow, Oregon grape, salal, buck brush and fern.	
	Wagon trail line betw sec. 19 & 30.	
	Desc. 218 ft. over W. slope, through heavy second growth timber and dense undergrowth.	
4.45	South Fork of the Walla Walla River, 35 lks. wide, course S.; asc. 1227 ft. over broken E. slope.	
6.00	South Fork of the Walla Walla River Trail, brs. N. and S.	
16.00	Small ravine, course SE.	
40.00	Set an iron post, 3 ft. long, 1 in. diam., 4 ins. in the ground to solid rock and in a mound of stone to top, for $\frac{1}{4}$ sec. cor., with brass cap marked	
	$\begin{array}{r} \frac{1}{4} S 19 \\ \frac{1}{4} S 30 \\ 1932 \end{array}$	
	from which	
	A fir, 10 ins. diam., brs. N. 10° W., 42 lks. dist., marked $\frac{1}{4}$ S 19 B T.	
	A fir, 24 ins. diam., brs. S. 60° E., 59 lks. dist., marked $\frac{1}{4}$ S 30 B T	
	Continue to asc. 96 ft. over NE. slope.	
42.60	Spur, slopes SE.; desc. 549 ft. over broken SW. slope.	
64.00	Ravine, course S.; asc. 470 ft. over SE. slope.	
76.20	Spur, slopes SE.; desc. 180 ft. over SW. slope.	
80.00	Set an iron post, 3 ft. long, 1 in. diam., 5 ins. in the ground to solid rock and in a mound of stone to top, for cor. of lots 1, 2, 7, and 8, with brass cap marked	
	$\begin{array}{r} S19 \\ 7 8 \\ E 1 \\ S30 \\ 1932 \end{array}$	
	from which	
	A fir, 20 ins. diam., brs. N. 13° W., 83 lks. dist., marked L 7 S 19 B T.	
	A pine, 26 ins. diam., brs. S. 40° E., 155 lks. dist., marked L 1 S 30 B.T.	
	Continue to desc. 168 ft. over SW. slope.	
84.40	Ravine, course S. 30° W.; asc. 43 ft. over SE. slope.	
87.16	Intersect E. bdy. of T 5 N., R. 38 E.	
	Set an iron post, 3 ft. long, 2 ins. diam., 12 ins. in the ground to solid rock and in a mound of stone to top,	