

## S. South Bdy. of T. 5 S., R 30 E. W. M.

Chains		Feet
80.00	<p>Set Pine post on level for Cor. to Secs. 33 and 34.</p> <p>A Tamarack 10 ins. diam. brs. N. 38° W. 10 lks. dist.</p> <p>A Fir 5 ins. diam. brs. N. 31° E. 19 lks. dist.</p> <p>Land; surface rolling,</p> <p>Soil; 2nd and 3rd rate. Heavy timber with open glades.</p> <p>Pine, Fir, Tamarack and occasional Juniper. Mostly open, only a little underbrush.</p>	
40.00	<p>E. on a true line along the S. Bdy. of Sec. 34.</p> <p style="text-align: right;">Var. 21° 45' E.</p> <p>Set basalt stone 15 x 10 x 5 on slight S. slope for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>A Fir 10 ins. diam. brs. N. 51° W. 15 lks. dist.</p> <p>A Fir 24 ins. diam. brs. S. 8° W. 23 lks. dist.</p>	
80.00	<p>Set basalt stone 15 x 12 x 4 on level for Cor. to Secs. 34 and 35.</p> <p>A Pine 20 ins. diam. brs. N. 36° E. 168 lks. dist.</p> <p>No tree on N.W., raised mound of stone, three feet in diam. and 18 ins. high around Cor.</p> <p>Land; surface rolling,</p> <p>Soil; 2nd and 3rd rate, mostly heavy timber. Some scattering, occasional open glades, Pine, Fir and Tamarack.</p> <p>A few places of young timber, underbrush.</p>	
40.00	<p>E. on a true line along the S. Bdy of Sec. 35.</p> <p style="text-align: right;">Var. 19° 30' E.</p> <p>Set basalt stone 16 x 8 x 7 on S.E. slope for <math>\frac{1}{4}</math> Sec. Cor.</p> <p>A Pine 18 ins. diam. brs. N. 10° W. 43 lks. dist.</p> <p>A Pine 24 ins. diam. brs. S. 28° E. 61 lks. dist.</p> <p>Steep descent.</p>	
80.00	<p>Set basalt stone 20 x 8 x 4 on S.E. side of rocky point for Cor. to Secs 35 and 36.</p> <p>A Fir 16 ins. diam. brs. N. 44° E. 50 lks. dist.</p> <p>No tree on N.W., raised mound of stone around Cor.</p> <p>Land; surface very broken.</p>	