

Resurvey of a portion of the exterior of T. 5 S., R. 29 E.W.M.

Chains		Feet
	marked $\frac{1}{4}$ S.B.T.	
78.30	Rattle Snake Creek, 25 lks. wide, runs E.	
80.00	Set basalt stone 16 x 10 x 10 ins. 10 ins. in the ground for Cor. to Secs. 7, 12, 13 and 18, marked with, 2 notches on the N, and 4 notches on the S. edges, from which A Pine 10 ins. diam. brs. N. 20° E. 59 lks. dist. marked T. 5 S., R. 30 E., S. 7 B.T. A Pine 10 ins. diam. brs. S. 22° E. 99 lks. dist. marked T. 5 S., R. 30 E., S. 18 B.T. A Pine 10 ins. diam. brs. S. 50° W. 70 lks. dist. marked T. 5 S., R. 29 E., S. 13 B.T. A Pine 10 ins. diam. brs. 15 N. 42° W. 71 lks. dist. marked T. 5 S., R. 29 E. S. 12 B.T.	
	Land; rolling; Soil; 2nd rate. Densely covered with forests of Pine and Fir timber, 80 Chs. Thick undergrowth of Pine and Fir. 80 Chs.	
	N. bet. Secs. 7 and 12, Var. 21° E.	
40.00	Set a basalt stone 14 x 9 x 3 ins. 9 ins. in the ground for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ on W. face, from which, A Pine 10 ins. diam. brs. S. 69° W. 143 lks. dist. marked $\frac{1}{4}$ S.B.T. A Pine 20 ins. diam. brs. N. 40° E. 119 lks. dist. marked $\frac{1}{4}$ S.B.T.	
80.00	Set a post 4 ft. long, 4 ins. sq. 24 ins. in the ground for Cor. to Secs. 1, 6, 7, 12. Marked, T. 5 S., S. 6 on the N.E. R. 30 E. S. 7 on the S.E. R. 29 E., S. 12 on the S.W. S. 1 on the N.W. faces with, 1 notch on the N., and 5 notches on the S. edges, from which, A Fir 8 ins. diam. brs. N. 17° E. 60 lks. dist.	