

Subdivisional Lines of T. 5 S., R. 30 E., W.M.

Chains		Feet
	<p>marked T. 5 S., R. 30 E., S. 30 B.T.</p> <p>A Pine, 18 ins. diam. brs. N. 75° W., 155 lks. dist.</p> <p>marked T. 5 S., R. 30 E., S. 19 B.T.</p> <p>Land; rolling,</p> <p>Soil; 2nd rate.</p> <p>Densely covered with forest of pine, fir & tamarack timber</p> <p>80. Chs.</p>	
<hr/>		
	E. on random line bet. Secs. 20 & 29.	
		Var. 20° E.
18.00	Ravine, course S.E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
74.00	Descend abruptly, course N.E. and S.	
80.14	Intersect N. and S. line, 20 lks. S. of Cor. to Secs. 20, 21, 28 & 29.	
	Thence I run,	
	S. 89° 51' W. on true line bet. Secs. 20 and 29, with same	
	Var.	
40.07	Set pine post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which,	
	A Pine, 8 ins. diam. brs. S. 7° W., 12 lks. dist.	
	marked $\frac{1}{4}$ S.B.T.	
	A Pine, 8 ins. diam. brs. N. 78° E., 4 lks. dist.	
	marked $\frac{1}{4}$ S.B.T.	
80.14	The Cor. to Secs. 19, 20, 29 & 30.	
	Land; rolling,	
	Soil; 2nd rate.	
	Densely covered with forests of pine, fir & tamarack,	80.14
	Chs.	
<hr/>		
	W. on random line bet. Secs. 19 and 30.	
		Var. 20° E.
10.60	Brook, 6 lks. wide, course S.	
32.50	" 3 " " " "	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
54.00	Brook, 4 lks. wide, course S.	