

Exterior Lines, T.5 S., R.31 E., W. M.

Chains.

62.00 Spring, 3 chs. E. of line.  
 74.00 Leave heavy timber, course E. & W.  
 80.00 Set basalt stone, 14 x 12 x 10 & post, in mound of stone,  
 on N.E. slope, for Cor. to Secs. 24, 25, 19 & 30. No  
 trees within distance.  
 Land; surface rolling & some broken, in places.  
 Soil; 2nd & 3rd & some 1st rate.  
 Heavy timber, pine, tamarack & fir on most of this mile.  
 Good grass, much good farming land.

N. on E. Bdy. of Sec. 24.

Var.19°45'E.

40.00 Set basalt stone, 18 x 10 x 8, on slight N. slope, for  $\frac{1}{4}$   
 Sec. Cor.  
 A pine, 14 ins. diam., brs. N.77°E., 164 lks. dist.  
 No other tree.  
 80.00 Set stone, 18 x 12 x 10 & post, in mound of stone, on level,  
 for Cor. to Secs. 13, 24, 18 & 19.  
 Land; surface, nearly level.  
 Soil; 2nd & 1st rate.  
 Only a few scattering pine trees. Excellent grass.  
 This is excellent farming land and well suited for grain  
 producing.

N. on E. Bdy. of Sec. 13.

Var.20°15'E.

22.00 Brook, 20 lks. wide, course N.W.  
 40.00 Set basalt stone, 18 x 10 x 7 ins., in mound of stone, on  
 level, for  $\frac{1}{2}$  Sec. Cor.  
 80.00 Set basalt stone, 18 x 10 x 7 & post, in mound of stone, on  
 level for Cor. to Secs. 12, 13, 7 & 18.  
 A pine, 8 ins. diam., brs. N.4°W., 362 lks. dist.  
 No other trees.  
 Land; surface level.  
 Soil; 2nd, 3rd & 1st rate.  
 Good grass. Large part of it well adapted to farming.