

Subdivisional Lines, T.5 S., R.31 E., W. M.

Chains	
80.00	<p>Cor., near middle of creek bed, of Camas creek, course N.W. I offset, S.50 lks. and set Set basalt stone, 18 x 8 x 8, on S. bank of creek, in mound of stone, for Cor. to Secs. 14, 15, 22 & 23. A willow, 7 ins. diam., brs. N.70°W., 127 lks. dist. A willow, 8 ins. diam., brs. S.54°W., 173 lks. dist. Land; surface S.64 chs. broken & rolling, N. 14 chs. level. Soil; 2nd, 3rd & 1st rate. Heavy pine, tamarack & fir timber on S. 64 chs. Some willow near creek. Valley is excellent farming land.</p>
	<p>E. on random line bet. Secs. 14 & 23. Var.19°50'E.</p>
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.
80.52	<p>Intersected N. & S. line, 72 lks. S. of Cor. to Secs. 13, 14, 23 & 24, from which Cor., I run S.89°29'W. on true line bet. Secs. 14 & 23. Var.19°40'E.</p>
46.00	<p>Alby house brs. N.55°W. " " " N. & creek, course S.W.</p>
40.26	<p>Set basalt stone, 14 x 10 x 5, on level, in mound of stone for $\frac{1}{4}$ Sec. Cor.</p>
49.00	Mr. Root's house brs. N.350 lks.
80.52	<p>The Cor. to Secs. 14, 15, 22 & 23. Land; surface nearly level. Soil; 1st rate. Good grass, excellent farming land; occasional bunches of willows.</p>
	<p>N. bet. Secs. 14 & 15. Var.19°50'E.</p>
1.00	Leave creek bed, course N.W.
5.00	House brs. N.66°E.
20.00	House brs. S.34°E.
40.00	Set basalt stone, 18 x 10 x 7, on level, for $\frac{1}{4}$ Sec. Cor.
41.00	Leave creek bottom prairie.