

Subdivisional Lines of T. 5 S., R. 32 E. W.M.

Chains		Feet
	Cabin and Corral, brs. N. 24° W.	
51.50	" " " " W.	
62.00	Enter timber, course E. and W.	
80.00	Set basalt stone, 14 x 12 x 4 in mound of stone in swale for Cor. to Secs. 1, 2, 11 & 12.	
	A Pine, 28 ins. diam. brs. N. 42° E., 96 lks. dist.	
	A " 11 " " " S. 55° E., 6 " "	
	A " 14 " " " S. 33° W., 14 " "	
	A " 30 " " " N. 10° W., 74 " "	
	Land; surface undulating	
	Soil; 2nd and 3rd rate. Pine and Tamarack timber on N. 18 Chs. Good grass. Larger part good farming land.	
	E. on a random line bet. Sec. 1 & 12	
		Var. 21° 00' E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
70.30	Intersected E, Bdy, 32 lks. S. of Cor. to Sec. 1 & 12, from which Cor. I run	
	S. 89° 46' W. on a true line bet. Sec. 1 & 12	
		Var. 20° 45' E.
16.00	Spring branch, course N.W.	
40.15	Set basalt stone, 14 x 12 x 10 on W. slope for $\frac{1}{4}$ Sec. Cor.	
80.30	The Cor. to Sec. 1, 2, 11 & 12	
65.68	Enter Timber, N.E. and S.W. Land; surface, rolling	
	Soil; 3rd and 2nd rate. Some Pine timber in scattering groves groves. Good grass. Small part good farming land.	
	N. on a random line bet. Sec. 1 & 2	
		Var. 21° 00' E
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.08	Intersect N. Boundary, 32 lks. W. of Cor. to Sec. 1 and 2, from which Cor. I run	
	S. 00° 14' W. on a true line bet. Sec. 1 & 2	
		Var. 21° 00' E.
40.08	Set basalt stone, 12 x 10 x 8 on N.E. face of creek bluff	