

## Subdivisional Lines of T. 5 S., R. 32 E., W.M.

Chains		Feet
	A Pine, 30 ins. diam. brs. S. 48° E., 63 lks. dist.	
61.00	Brook, 12 lks. wide, course N	
69.00	Leave timber, course N. and S.	
80.46	The Cor. to Secs. 29, 30, 31 & 32	
	Land; surface very broken	
	Soil; 3rd rate. Pine, Tamarack & Fir timber, Grass in open glades.	
<hr/>		
	N. bet. Sec. 29 & 30	
		Var. 19° 15' E.
5.50	Enter timber, course N.W. and S.E.	
40.00	Set basalt stone, 20 x 14 x 10 on N. slope for $\frac{1}{4}$ Sec. Cor.	
	A Pine, 32 ins. diam. brs. N. 73° E., 43 lks. dist.	
	A Pine, 20 ins. diam. brs. N. 21° W., 36 lks. dist.	
80.00	Set basalt stone, 14 x 12 x 8 on N. slope for Cor. to Sec. 19, 20, 29 & 30.	
	A Pine, 32 ins. diam. brs. N. 5° E., 56 lks. dist.	
	A Pine, 40 ins. diam. brs. S. 50° W., 100 lks. dist.	
	A Pine, 38 ins. diam. brs. N. 37° W., 127 lks. dist.	
	No tree S.E.	
	Land; surface S. 20 Chs., very steep, N. 60 Chs. more gradual descent,	
	Soil; 1st, 2nd and 3rd rate. Pine, Tamarack and Fir timber. Heavy on S. 60 Chs., N. 20, scattering. Good farming land.	
		June 9, 1881
<hr/>		
	E. on a random line bet. Sec. 20 & 29	
		Var. 19° 30' E.
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.75	Intersected N. and S. line, 32 lks. S. of Cor. to Secs. 20, 21, 28 & 29, from which Cor. I run	
	S. 89° 46' W. on a true line bet. Sec. 20 & 29	
		Var. 20° 15' E.
25.00	William Johnson's house, brs. S. 11 Chs.	