

Subdivisional Lines of T. 5 S., R. 32 E., W.M.

Chains		Feet
	N. on a random line bet. Sec. 5 & 6 Var. 19° 45' E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.84	Intersected N. Bdy. 28 lks. E. of Cor. to Sec. 5 & 6, from which Cor. I run S. 00° 12' E. on a true line bet. Sec. 5 & 6 Var. 19° 15' E.	
39.84	Set basalt stone, 14 x 10 x 6 on level for $\frac{1}{4}$ Sec. Cor.	
79.84	The Cor. to Sec. 5, 6, 7 & 8 Land; surface undulating Soil; 2nd, 3rd and 1st rate. Good grass. Good farming land. June 11, 1881 Note:- Having set all the Cors. on the W. Bdy. myself last year, and finding them all as I left them, I merely state that I find them all correct.	
	General Description	
	The surface in the S.W. Cor. is quite broken, almost mountainous, the remainder which is far the largest part is either level or undulating excep along the creeks, which is also broken.	
	The soil is principally good, 2nd rate a large part is first rate and well adapted to agricultur, about $\frac{1}{4}$ is 3rd rate and is only valuable for timber or grazing,	
	It is well watered with springs and streams. There is suf- ficient of good timber, for all purposes of improvement.	
	There are a number of claims taken on which improvements are only just begun. Four claims to be permanent, one on Sec. 35. Two on Sec. 29, and one on 18 & 19	