

Chains

- stone, still in place; no trace of the old post remains.
- I reestablish this Cor. at the same point by setting a basalt stone, 18 x 10 x 4 in., 12 ins. in ground, for Cor. of Secs. 19, 24, 25 & 30, marked with 2 notches on S., and 4 notches on N. edges; dig pits, 18 x 18 x 12 ins., in each Sec., 5½ ft. dist. and raise mound of earth, 4 ft. base, 2 ft. high, W. of Cor.
- From this Cor., the initial point of survey of Oregon-Washington Bdy. line, on E. bank of Columbia River, brs. N.31° 53' E., 135.63 chs. dist.
- Thence I run
- S., retracing W. Bdy. of Sec. 30.
- 40.00 All evidence of old ¼ Sec. Cor., described as a post, with pits & mound of earth, has entirely disappeared.
- Set temp. ¼ Sec. Cor.
- 79.10 My line falls 120 lks. E. of old Cor. of Secs. 25, 30, 31 and 36, as identified by the old post and charcoal deposit still in place.
- The line brs. S.0°52' W.
-
- From the old Cor. of Secs. 25, 30, 31 & 36, I run
- S., retracing W. Bdy. of Sec. 31.
- 39.68 My line falls 5 lks. W. of ¼ Sec. Cor., which is a decayed post, with marks still legible.
- The line brs. S.0°4' E.
- Thence from the old ¼ Sec. Cor.
- I run
- S., retracing W. Bdy. of Sec. 31.
- 39.28 My line falls 21 lks. E. of Cor. of Tps. 5 & 6 N Rs 30 & 31 E. At this Tp. Cor., I find the stump of the original bearing tree, a juniper, 20 ins. diam., S.69°30' E., 5.50 chs. dist., cut off about 12 ins. above surface of the ground, still showing marks on lower facing; also stump of original bearing tree, a juniper, 24 ins. diam., N.8° 30' E., 3 chs. dist., cut off at surface of the