

Resurvey West Bdy., T 6 N R 31 E W M.

Chains

N.0°4' W., counting the distance from the $\frac{1}{4}$ Sec. Cor.

Over high, rolling table land.

39.68 To the old Cor. of Secs. 25, 30, 31 & 36, which I now de-
stroy and reestablish at the same point as follows:

Set basalt stone, 22 x 12 x 10 ins., 16 ins. in ground, for
Cor. of Secs. 30 & 31 only, mkd. with 1 notch on S. and
5 notches on N. edges; dig pits, 24 x 24 x 12 ins., in
each Sec., 6 ft. dist., & raised mound of earth, 4 ft.
base; 2 ft. high, E. of Cor.

Land; level, rolling & mountainous.

Soil; sandy, 2nd & 3rd rates.

Timber; juniper.

Undergrowth; sage.

From the Cor. of Secs. 30 & 31, above described, I run

N.0°52' E., resurveying W. Bdy. of Sec.30.

Over high, rolling table land.

Apportioned distance.

39.55 Set basalt stone, 20 x 15 x 12 ins., 15 ins. in ground, for
 $\frac{1}{4}$ Sec. Cor. on W. Bdy. of Sec.30, mkd. $\frac{1}{4}$ on E. face;
dig pits, 18 x 18 x 12 ins., N. & S. of stone, 3 ft.
dist., and raise mound of earth, $3\frac{1}{2}$ ft. base, $1\frac{1}{2}$ ft.
high, E. of Cor.

All indications of the old Cor. have disappeared.

49.00 Leave table land, brs. N.E. & S.W. and begin steep descent.

74.10 Enter valley, 700 ft. below table land, brs. N.E. & S.W.

79.10 The Cor. of Secs. 19, 24, 25 & 30, heretofore described.

Land; level, rolling. & mtns.

Soil; sandy & stony, 2nd & 4th rates.

No timber.

Undergrowth; sage & greasewood.

Being unable to find the Meander Cor. of Fractional Secs.

19 & 24 on W. Bdy. of T 6 N R 31 E., I

Commence at the Cor. of Secs. 19, 24, 25 & 30, above de-
scribed.