

Subdivisional Lines, T 6 N R 30 E W M.

Chains	
9.00	Descend from bench.
14.31	A road brs. N.E. & S.W.
17.06	The same road brs. N.W. & S.E.
20.00	Bottom of ravine, course N.E. ; leave loose sand.
28.50	Top of small spur, sloping N.E.; begin vert steep descent.
34.50	Enter flat bottom of Juniper Canyon, at foot of rimrock, 12 ft. high, course N.W.
40.00	Set basalt stone, 18 x 12 x 10 ins., 12 ins. in ground, for $\frac{1}{4}$ Sec. Cor., mkd. $\frac{1}{4}$ on W. face; dig pits, 18 x 18 x 12 ins., N. & S. of stone, 3 ft. dist. & raise mound of earth, $3\frac{1}{2}$ ft. base, $1\frac{1}{2}$ ft. high W. of Cor.
43.31	Leave canyon & ascend.
44.88	Center line of main track of O.W.R. & N. R.R., brs. N.65° 48' E. and S.65°48' W.
53.00	Wagon road brs. N.W. & S.E.
55.72	To left bank of Columbia River. Set basalt stone, 14 x 10 x 8 ins., 9 ins. in ground, for Meander Cor. for fracl. Secs. 34 & 35, mkd. M C on N. face, with 2 grooves on E. face; from which A juniper, 9 ins. diam., brs. N.72° E., 144 lks. dist., mkd. T 6 N R 30 E S 35 M C B T. No other trees available; dig pit, 36 x 36 x 12 ins. 8 ft. S. of stone & raise mound of earth, 4 ft. base, 2 ft. high, S. of Cor. Land; first 40 chs. mountain slopes & benches; remainder level valley. Soil; loose, sandy ash, 1st to 4th rates. No timber, except a few scattering juniper along river bank. Undergrowth; sage, good bunchgrass.
	I now begin at the Cor. of Secs. 25, 26, 35 & 36, heretofore described Thence I run W. on true line, bet. Secs. 26 & 35.